










SITE RULES


All Exhibitors or Contractors working on site during the Construction phase (Build-up) and Dismantling phase (Breakdown) must adhere to the site rules below.

| | |
|---|---|
|  | You should not enter site if: <ul style="list-style-type: none"> You have any symptoms associated with COVID-19 You have tested positive for COVID-19 |
|  | If you develop COVID-19 symptoms whilst onsite you must leave site immediately |
|  | No Unauthorised Access. Children under the age of 16 will not be permitted. |
|  | No smoking in exhibition halls or marked outside areas. |
|  | Drinking of alcohol onsite during the build up and breakdown phase is forbidden. The taking of illegal drugs is strictly forbidden at all times. |
|  | Site speed limit of 5mph must be adhered to at all times. |
|  | PPE including high visibility clothing and safety footwear must be worn by all personnel onsite during the build up and breakdown. Open toed shoes will not be permitted. |
|  | Hard hats must be worn in designated areas where overhead work taking place. |
|  | A permit to work is required before any hot working commences. |
|  | Machine and tool guards must always be used. Non-guarded machinery will not be permitted to be used and non-guarded tools will be confiscated. |
|  | Emergency Gangways and fire exits must be kept clear at all times. |
|  | Practice good respiratory hygiene and regularly wash your hands. |
|  | Trailing cables must be minimised wherever possible. Where they are required they must be clearly identified and used for the minimum time possible. |
|  | All temporary scaffold towers must be correctly built in line with manufacturer's instructions and persons erecting must be suitably trained and competent. |
|  | All working at height must be planned to minimise risks involved so far as is reasonably practicable. |
|  | All Accidents, Incidents and near misses must be reported immediately to the Organisers office 4.2 located outside Hall 4. Telephone number 04 306 4808. |

Site Warnings:

| | |
|---|--|
|  | Caution – Slip & Trip Hazards |
|  | Caution – Fork Lift trucks will be operating |
|  | Caution – Crane operations & overhead working in designated areas |
|  | Caution – Vehicle movement |
|  | Caution – Working at height, danger of falling |
|  | Caution – Live electrical installations |
|  | Caution – Guard dogs on patrol |
|  | CCTV in operation |
|  | Unsafe working practices will not be tolerated. Work will ultimately be stopped and persons involved escorted offsite if practice or issue is not rectified. |

Useful information:

| | |
|--|---|
|  | The First Aid room is adjacent to the entrance of Hall 5, just off concourse 2. It can be contacted through organiser's office or any security personnel at each hall entrance or if you are using a mobile phone +971 (0)4 306 4040. A qualified First Aider will be either dispatched to the First Aid room or directly to any accident area if required. |
|--|---|

- All **vehicles** requiring access to the halls must report to the holding area.
- Access to the halls will be with a Contractor Badge issued by DWTC
- There are many catering outlets in the concourse at DWTC.
- There are permanent **toilet facilities** available within the hall.
- Drinking water is available to be purchased from the outlets in the concourse at DWTC.



Site safety starts here

SAFETY SHOWS



In the business of building businesses